



FOR OFFICE USE

Public Works #	
Code 212	
Inspections #	
Code 207	
Public Works fee	
Inspection fee	
Total fee	
Receipt #	

Driveway Permit

Project Location/Property Owner Information		Applicant/Contractor Information		
Name:	Applicant:			
Address:	Company:			
City/State/Zip:	Address:			
Phone:	City/State/Zip:			
Email:	Phone:			
Email:				
Project Information				Fee
Concrete sidewalk	New			\$5
Sidewalk rehabilitation	Mudjacking	Grinding	Replace	No Fee
Driveway apron	New	Replace		\$10
Curb opening	New	Replace		\$10
Culvert	New	Replace		\$10
Driveway *Site plan required*	New	Replace	Addition	\$40
Schedule Required Inspection				
Please call to schedule an inspection. Public Works must be given a 2-day notice before commencing work				
Permit Approval				
Upon signature this becomes a permit to conduct the above-described work. Permits expire 6 months after the issue date.				
Approval Conditions:				
Public Works Signature:				Date:
Building Inspector Signature:				Date:
Applicant Signature and Statement				
I certify that the information provided on this form is complete and accurate and hereby agree to comply with all applicable statutes of the State of Wisconsin and ordinance of the Village of Little Chute, Wisconsin. I further understand that the issuance of this permit creates no legal liability, expressed or implied, on the Village of Little Chute. It is unlawful to do any work in the public right-of-way without an approved permit. Contractors are required to provide Little Chute with a certificate of insurance and a \$25,000 bond for work in the right of way.				
Signature:				Date:



Village of Little Chute
108 W Main St.
Little Chute, WI 54140

Public Works Department
Phone 920-423-3865


Inspections Department
Phone- 920-423-3871
Email- buildinginspector@littlechutewi.org

GENERAL NOTES FOR DRIVEWAYS AND SIDEWALKS

- LOCATIONS FOR DRIVEWAY OPENINGS AND LENGTH OF TRANSITION AREAS FOR DRIVEWAYS SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.
- ALL RESIDENTIAL DRIVEWAY APRONS AND SIDEWALK THROUGH DRIVEWAYS SHALL BE REPLACED WITH 6-INCH CONCRETE OVER 3" OF 1-1/4" BASE AGGREGATE DENSE.
- ALL COMMERCIAL DRIVEWAY APRONS AND SIDEWALK THROUGH DRIVEWAYS SHALL BE REPLACED WITH 7-INCH CONCRETE OVER 3" OF 1-1/4" BASE AGGREGATE DENSE.
- NO STEEL (WIRE MESH, REBAR, ETC.) ALLOWED IN FLATWORK WITHIN PUBLIC RIGHT OF WAY.
- CONTRACTOR SHALL DIE STAMP ALL CONCRETE Poured WITHIN PUBLIC RIGHT OF WAY.



PROFILE PARALLEL TO CENTERLINE OF ROADWAY



CONCRETE DRIVEWAY

N.T.S.